# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/RD/WORK_INDENT17823

## APPROVED SCHEDULE - B

**EE/BTP/BBMP/E-PMT/01/2015-16**

**Improvements to Roads and Drains at Singapura Paradise & Surrounding Roads in Ward No. 11 Vidyaranyapura Sub Division**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of B B UMESHA | | |
|---|---|---|---|---|---|---|
| | | | | In Figures | | In Words |
| 1 | 832.5 | Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work | Cum | 75.6 | 62937.00 | Rupees Seventy Five and Sixty Paise Only |
| 2 | 2214 | Removing B.S Slab of Drain and stacking etc complete as per specifications and directions of engineer in charge of the work | Sqm | 58.32 | 129120.48 | Rupees Fifty Eight and Thirty Two Paise Only |
| 3 | 2214 | Refixing stone slabs of drains and pointing in C.M (1:3) etc complete as per specifications and directions of engineer in charge of the work | Sqm | 75.6 | 167378.40 | Rupees Seventy Five and Sixty Paise Only |
| 4 | 832.5 | Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work | Cum | 1438.56 | 1197601.20 | Rupees One Thousand Four Hundred Thirty Eight and Fifty Six Paise Only |
| 5 | 5550 | Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WBM, WMM including cleaning of road surface and spraying primer at the rate of 0.60 Kg / sqm using mechnical means etc complete as per specifications and directions of engineer in charge of the work | Sqm | 31.32 | 173826.00 | Rupees Thirty One and Thirty Two Paise Only |
| 6 | 138.75 | Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. with 100-120 TPH capacityH.M.P with sensor paver Gr-II (25 mm to 30 mm) with 5 % VG-30 Bitumen etc complete as per specifications and directions of engineer in charge of the work | Cum | 8475.84 | 1176022.80 | Rupees Eight Thousand Four Hundred Seventy Five and Eighty Four Paise Only |
| 7 | 832.5 | Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. etc complete as per specifications and directions of engineer in charge of the work | Cum | 73.57 | 61247.03 | Rupees Seventy Three and Fifty Seven Paise Only |
| | | | | | 2968132.91 | |

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

26/5/16